



**NOTE:**

1. REFER TO GENFLEX™ WEBSITE FOR MOST CURRENT INFORMATION.
2. NAILING AND METAL COUNTER-FLASHING ARE NOT REQUIRED IF MEMBRANE IS RUN UP AND COVER CURB WALL PRIOR TO INSTALLATION OF R.T.U.
3. METAL COUNTER-FLASHING SHALL BE 24 GAUGE PRE-FINISHED STEEL OR .032" MIN. ALUMINUM FORMED WITH HEMMED LOWER EDGE MOUNTED TIGHTLY TO UNDERSIDE OF MECHANICAL UNIT.
4. MAXIMUM 10" (254 mm) LONG FASTENER. (NOTE: WOOD BLOCKING MAY BE SUBSTITUTED FOR INSULATION TO REDUCE THE FASTENER LENGTH REQUIREMENT).
5. BAR ANCHOR MAY BE USED IN LIEU OF 2" METAL PLATES. REFER TO "EZE-PS-BT" DETAILS FOR SPECIFIC BASE TIE-IN INFORMATION, REQUIREMENTS, AND OPTIONS.
6. INSTALL METAL WORK IN ACCORDANCE WITH CURRENT SMACNA RECOMMENDATIONS.
7. APPROVED PRIMERS INCLUDE GENPRIME AND ALL PURPOSE LVOC PRIMER.
8. APPROVED PRIMER REQUIRED ON ALL VERTICAL SURFACES.



**TERMINATION AT R.T.U. WITH PEEL & STICK RPS  
(UNIT FLANGE MOUNTED TO SUBSTRATE)**

ACCEPTABLE SYSTEMS: EZ EPDM PEEL & STICK™ SELF ADHERED

(800) 443-4272 www.genflex.com

MAXIMUM WARRANTY: 20 Years

ISSUE / REVISION  
DATE:

07/28/2023

NOT TO SCALE

DETAIL NO.

EZE-PS-T-08